

Private Property Inflow And Infiltration Inspection Procedures For Contractors

Purpose

The following instructions and standards are intended for property owners and their contractors when choosing to use a private contractor to complete the Point of Sale Sanitary Sewer Service Inflow and Infiltration (I/I) Inspection. Private inspection contractors will need to complete the inspection using the City of Orono's Inflow/Infiltration Inspection Form, available on the City website. Inspectors will require access to the basement or lowest level in the home or building and access to all sewer cleanouts, sump pump(s), and sump pump plumbing. The televised portion of the I/I inspection is to note defects in the sanitary sewer lateral, which result in infiltration and ex-filtration. The purpose of the private property inflow and infiltration (I/I) inspection is to reduce the flow of clear water into the sanitary sewer system via cross connections (inflow) from sump pumps, foundation drains, roof leaders, cisterns, and other clean water sources connected to the sanitary sewer system. In addition, the program aims to reduce indirect flow of clean water into the sanitary sewer system (infiltration) through pipe and pipe joint defects.

Video / Picture Standards

- · The video report will be in a MPEG format
- Still photos will be in a JPEG format
- Video reports can be submitted on thumb drives or a USB hard drive.
- Reference the start and end of each video segment as it begins.
- · Footages along the sewer service line must be shown on the video report.
- The video camera shall be guided forward at a moderate to slow pace along the bottom of the pipe.
- The camera shall stop at any connection.
- The camera shall stop at any unusual instances that are viewed while in progress and provide a more detailed and longer view of the specific instance (i.e. bad joint, dirt in lines, settlement in line, etc.).

Sewer Service Inspection Criteria And Process

- Inflow/Infiltration Compliance Inspection form must be completely filled out for the inspection to be complete.
- The inspector is required to note all defects and footage location in the sanitary sewer lateral on the compliance inspection form and an audio description recorded on USB Thumb drive or hard drive.
- The sewer service inspection must the service pipe from before it exits the building to the sewer main.
- All connections must be verified by flowing water into drains, referencing the source, and reporting them on the video
- Any connection that cannot be verified is considered to be an unknown connection and must be exposed to verify source.
- All cleanouts are required to be opened and inspected (include photos of the opened cleanout riser); cleanout inspection requires documented footage location on the form and audio description recorded on USB Thumb drive or hard drive.

- All floor drains will need to be opened and inspected (include photos of the drain, the surrounding area, and the nearest foundation wall).
- Any foundation drains found will need to be opened and the discharge point verified (include photos).
- All external drains will need to be opened and the discharge point verified
- Defects/items that require documentation include, but are not limited to:
 - > roots
 - > offset pipe joints
 - > mineral deposits
 - > unknown deposits
 - > sag/pipe deflection
 - > cracked pipes
 - > chipped pipes
 - > Pipe size transitions
 - > length of service
 - > location of all cleanouts
 - > broken / damaged or missing pipe foundation drain connections (including photos).

Private Property Inflow And Infiltration Inspection Procedures For Contractors

Sewer Service Fu	orther Investigation Issues	
Properties foundunable to accesunable to compunknown conne	I in need of further investigation he is sewer lateral due to un-located of lete inspection of sewer lateral du actions (unable to verify connections	e to roots, solid deposition, crushed pipe, etc on flowing water into sewer lateral
Sump Pump/Roof	Leader Inspection Criteria And P	rocess
• Inflow/Infiltrati must have the "Su Drains" sections of inspection to be co • Every sump pure be inspected (included) basket, the surrour pipe, both interior sump pumps must • Sump pump discorrigid pipe. Flexible	con Compliance Inspection form amp Pumps" and "Foundation completely filled out for the complete. Import the property is required to uding photos of the opened anding area, and the discharge and exterior). Total number of the noted. I be noted. I charge piping is required to be epipe, shut-off valves, if wyes are not allowed.	 Correctly plumbed sump pump discharges outside of the building using rigid pipe. Pipe discharge should be a minimum of 10-feet from building. Sump pumps that do not discharge outside are incorrectly plumbed and are considered non-compliant. Roof leaders are required to discharge outside of the building; any roof leaders and or cisterns discharging into foundation drains are non-compliant.
 Property owner is to sign the completed Inflow/Infiltration Compliance Inspection form and retain a copy for their records. A copy of the completed Inflow/Infiltration Compliance Inspection form and video link is required to be delivered to the City of Orono for review. The City's Utilities Supervisor or his/her designee will review the video and compare it with the completed Inflow/Infiltration Compliance 		The City will issue either a Certificate of Compliance or a Correction Notice once the review is complete. If a correction notice is issued, the required repairs must be made and a post-repair televised inspection must be performed in order to receive Certificate of Compliance. The completed forms will be mailed to the address on the Inflow/Infiltration Compliance Inspection form, unless a different address is noted.
Contractor comple understands the confor Contractors.	ting the Inflow and Infiltration Conditions of the Private Property In	flow and Infiltration Inspection Procedures
Company name Johns Sewal & Didin Cleaning Inspector name Mike Marales Copy of plumbers license 71N		
On file 45.26	724K(or) Attached	
License number		Bond Date SecurA 6-18-25
Staff Use Only		
Date Received	Staff Name and Signature	
6-18-25	Heather Smieja	Idealth Suy